

We, Pipe Hangers and Supports Pvt Limited believe that safe workplaces are as much about having the right standards and engineering controls in place as they are about ensuring that inattentive and uncontrolled high risk personal behaviors are eliminated. It is important that our internal processes must be followed and to identify hazards and risks specific to our workplace. Here are the few topics which we have implemented in our factory for ensuring the safety of employees.

❖ Mock Fire drill conducted at our Factory



❖ Painter training given by Paint Manufacturer (Asian Paints) for our Employees



❖ Welder safety being patrolled Third Party Inspectors.



- ❖ Blasting operators with full safety suit



- ❖ Furnace operators with full safety apron





❖ Medical Check-up for all employees periodically



**SAFETY TRAINING PROGRAMME**  
**COMPANY NAME: PIPE HANGERS & SUPPORTS PVT LTD**  
**DATE: 31.10.2023 TIME: 11.00 AM TO 1.00 PM**



**TUBERCULOSIS AWARENESS PROGRAMME AND MEDICAL CAMP  
AT PIPE HANGERS AND SUPPORTS**







In addition to the above, we have listed the safety checks we are following at our factory

- ❖ Eye checkup for all employees
- ❖ Medical checkup for Welding/Blasting/Painting operators (Hematology/Spiro-metric test)
- ❖ Material Safety Data Sheet installed in Paint Storage area and protocols followed regularly
- ❖ Electrical earthing check (Megger Test) at 21 locations in our plant
- ❖ Load Test for EOT crane/Fork Lift/Mobile Crane/Lifting belts/Shackles
- ❖ Sensor Lamps installed in blasting/furnace areas
- ❖ Flash-back arrestor in all CNC/welding machines to avoid reverse flow of gases
- ❖ Installation of deadman switch/air cool helmet in blasting zone in case of emergency
- ❖ Safety shoes,masks,gloves made compulsory for all employees in factory
- ❖ Ensuring all areas are fitted with industrial sockets
- ❖ Caution boards/Restricted area marking done in Electrical panel board/UPS/Diesel storage area
- ❖ Siren/emergency assembly points are maintained properly
- ❖ Speed limit sign board/ Emergency contact numbers are displayed in all vehicles
- ❖ Periodic service done for EOT crane/Fork Lift/Mobile Crane
- ❖ Check list for safety maintained at all major points and checked periodically

For past newsletters please look up our website [www.pipehangers.in](http://www.pipehangers.in)


## About Pipe Hangers:

### A Global Solution to Spring Hangers and Supports

We are the leading manufacturer of spring hangers, supports & accessories. Over the past 39 years we have supplied to major power plants, refineries, nuclear installations & process industries in India & several International projects.

## Pipe Hangers & Supports Private Limited

### Ordering Information



- 1) Hot Load (Operating Load) in Kgs : \_\_\_\_\_
- 2) Thermal Movement / Travel (Direction + or -) in mm : UP (+) \_\_\_\_\_ mm
- 3) Type of Hanger Variable / Constant /Rigid : VariableEffort Support
- 4) For Constant Add Over Travel :  Yes  No
- 5) For Variable Springs Max Allowable % Load Variation : \_\_\_\_\_ %
- 6) Horizontal / Lateral Movement (If any) : 'X' Dir \_\_\_\_\_ mm / 'Z' Dir \_\_\_\_\_ mm
- 7) Hydro Load ( If any) : \_\_\_\_\_ Kgs
- 8) Model & Type of Support : \_\_\_\_\_
- 9) Assembly Length (From BOS/TOS to Pipe CL ) : \_\_\_\_\_ mm
- 10) Operating Temperature : \_\_\_\_\_ Deg C
- 11) Pipe Insulation Thk : \_\_\_\_\_ mm
- 12) Pipe Material : \_\_\_\_\_
- 13) Require Pipe Shoe for Foot Mounted Support :  Yes  No
- 14) For Foot Mounted Support Match Height :  Yes  No
- 15) Attachments like Lugs, Cleats Welded to Pipe in Scope :  Yes  No
- 16) Operating Load includes Wt of Accessories like Clamp, Tie Rods, Cleats, Lugs etc. :  Yes  No
- 17) Preferred Surface Protection / Painting : \_\_\_\_\_
- 18) For 'G' Type / Double / Trapeze type Hanger the Load Given above is for 1 assembly consisting of 2 Hangers / Individual Hanger :  Yes  No

